

# CARACAL RENTAL PUMP PACKAGE

**TECHNICAL DATA SHEET** 

### **TECHNICAL REFERENCE SPECS**

Pump Package	Caracal
Туре	Simplex
НР	3
Voltage	480/3
FLA	4
Connection Size	1.5" 150# Flg
Max Flow Condition	75 GPM @ 40 PSI
Max Boost Condition	16 GPM @ 68 PSI
Max Building Size	5 Floors Of Typical Office Building with Cooling Tower Load
Dry Weight	350 Lbs.



Caracal Rental Pump - Side View

# CLICK TO EMAIL & REQUEST RENTAL

## **RENTAL PUMP PACKAGE FEATURES**

- Rental Package is on a 24" X 48" X 73" cart with casters.
- Cougar Controls VFD Panel with Through the Door Disconnect and VFD Controller.
- Piping includes:
  - Isolation Valves
  - · Check Valve
  - Gauges
  - Pressure Sensing Devices
- Grundfos CR Series vertical multi-stage pump.
- · Field Install requirements (not included in Rental)

#### Field Plumbing Required

- Pipe to the suction and Discharge Connections on the package
- no isolation or check valves required

#### Field Electrical Required

- Incoming 480/3 Circuit to control panel
- 50FT SO cable pre-wired to control panel
- Components on skid are pre-wired to the control panel.
- Rental includes Start Up of the system.



Caracal Rental Pump - Iso View

