

CHEETAH CRE RENTAL PUMP PACKAGE

TECHNICAL DATA SHEET

TECHNICAL REFERENCE SPECS

Pump Package	Cheetah CRE
Туре	Simplex
НР	7.5
Voltage	480/3
FLA	9
Connection Size	2" 150# Flg
Max Flow Condition	120 GPM @ 70 PSI
Max Boost Condition	45 GPM @ 110 PSI
Max Building Size	8 Floors Of Typical Office Building with Cooling Tower Load
Dry Weight	460 Lbs.



Cheetah CRE Pump - CRE Side View

CLICK TO EMAIL & REQUEST RENTAL

RENTAL PUMP PACKAGE FEATURES

- Rental Package is on a 30" X 60" X 73" cart with casters.
- Cougar Controls VFD Panel with Through the Door Disconnect and VFD Controller.
- Piping includes:
 - Isolation Valves
 - Check Valve
 - Gauges
 - Pressure Sensing Devices
- Grundfos CR Series vertical multi-stage pump.
- Field Install requirements (not included in Rental)

Field Plumbing Required

- Pipe to the suction and Discharge Connections on the package
- no isolation or check valves required

Field Electrical Required

- Incoming 480/3 Circuit to control panel
- 50FT SO cable pre-wired to control panel
- Components on skid are pre-wired to the control panel.
- Rental includes Start Up of the system.



Cheetah CRE Pump - Iso View

